

MATERIAL LIST

G2436K Garage Plan

Standard W/ Truss Roof

This estimate is designed solely to provide the customer with a rough estimate of the amount of material used in the given project. The material estimate is based on normal and typical building and construction techniques. The actual amount of material used may vary from this estimate due to a number of factors. Consequently, no representation or warranty has been made that the amount of material used will not vary from the estimate.

	ITEM	CALC	SIZE	LENGTH	O.C.	QTY	
1	MAIN EXT STUDS		2X4	101.50	16"	73	EA
2	MAIN TREATED SILL		2X4			98	LF
3	MAIN EXT PLATES		2X4			344	LF
4	HEADER, (Ext Main Garage Door)	B04-T	3-1/8X13-1/2 GLB	17'		1	EA
5	HEADER, (Ext Main Door)	N/A	4X8	4'		2	EA
6	HEADER, (Main Window)	N/A	4X8	5'		2	EA
7	TRUSSES				24"	17	EA
8	TRUSSES (Ends)					2	EA
9	EAVE BLOCKING		2X	22.5"	24"	36	EA
10	H2.5 RAFTER TIE				24"	38	EA
11	ROOF SHEATH		1/2" CDX			1144	SF
12	ROOF FELT		30# Felt			1144	SF
13	ROOFING					1144	SF
14	BARGE RAFTERS		2X6	16'		4	EA
15	MAIN EXT WALL S.R. (Optional)		1/2" GYP.			882	SF
16	MAIN CEILING S.R. (Optional)		1/2" GYP.			864	SF
17	EXT WALL SHEATH		1/2" CDX			882	SF
18	EXT WALL VAPOR		15# Felt			882	SF
19	EXT SIDING (See Plan)		Varies			882	SF
20	CONCRETE					16.99	CY
21	ANCHOR BOLTS		1/2"		48"	25	EA
22	HOLD DOWNS		HD3B W/SSTB16			8	EA
23	WIRE MESH		6X6 W1.4 X W1.4			864	SF

MATERIAL LIST

G2436K Garage Plan

Standard W/ Framed Roof

This estimate is designed solely to provide the customer with a rough estimate of the amount of material used in the given project. The material estimate is based on normal and typical building and construction techniques. The actual amount of material used may vary from this estimate due to a number of factors. Consequently, no representation or warranty has been made that the amount of material used will not vary from the estimate.

	ITEM	CALC	SIZE	LENGTH	O.C.	QTY	
1	MAIN EXT STUDS		2X4	93.50	16"	72	EA
2	MAIN TREATED SILL		2X4			96	LF
3	MAIN INT PLATES		2X4			18	LF
4	MAIN EXT PLATES		2X4			342	LF
5	MAIN INT STUDS		2X4		16"	6	EA
6	UPPER CEILING S.R. (Optional)		1/2" GYP.			1000	SF
7	HEADER, (Ext Main Garage Door)	B04-F	5-1/8X16-1/2 GLB	19'		1	EA
8	HEADER, (Ext Main Door)	N/A	4X8	4'		2	EA
9	HEADER, (Main Window)	N/A	4X8	5'		2	EA
10	RAFTERS	B02-F	2X8	16'	16"	56	EA
11	EAVE BLOCKING		2X	14.5"	16"	54	EA
12	H2.5 RAFTER TIE				16"	56	EA
13	ROOF SHEATH		1/2" CDX			1144	SF
14	ROOF FELT		30# Felt			1144	SF
15	ROOFING					1144	SF
16	BARGE RAFTERS		2X6	16'		4	EA
17	MAIN EXT WALL S.R. (Optional)		1/2" GYP.			864	SF
18	MAIN INT WALL S.R. (Optional)		1/2" GYP.			108	SF
19	MAIN CEILING S.R. (Optional)		1/2" GYP.			864	SF
20	EXT WALL SHEATH		1/2" CDX			864	SF
21	EXT WALL VAPOR		15# Felt			864	SF
22	EXT SIDING (See Plan)		Varies			864	SF
23	CONCRETE					16.79	CY
24	JOISTS	B03-F	2X12	24'	16"	28	EA
25	RIM JOIST					120	LF
26	UPPER FLOOR PLYWOOD		5/8"			864	SF
27	RIDGE BEAM	N/A	2X10	36'		1	EA
28	ANCHOR BOLTS		1/2"		48"	24	EA
29	HOLD DOWNS		HD3B W/SSTB16			8	EA
30	WIRE MESH		6X6 W1.4 X W1.4			864	SF