

MATERIAL LIST

G2442B Garage w/ Storage

This estimate is designed solely to provide the customer with a rough estimate of the amount of material used in the given project. The material estimate is based on normal and typical building and construction techniques. The actual amount of material used may vary from this estimate due to a number of factors. Consequently, no representation or warranty has been made that the amount of material used will not vary from the estimate.

| | | CALC | SIZE | LENGTH | DIST. | O/C | QTY. | |
|----|-------------------------------|------|------------------|--------------|--------|-----|-------|----|
| 1 | EXT. STUD (Main) | | 2x6 | 96" (varies) | 71.00 | 16 | 54 | EA |
| 2 | EXT. STUD (Upper) | | 2x6 | 80" (varies) | 124.00 | 16 | 94 | EA |
| 3 | TREATED SILL | | 2x6 | | 113.00 | | 113 | LF |
| 4 | PLATES (Main & Upper) | | 2x6 | | 264.00 | | 776 | LF |
| 5 | DOOR HEADER, Garage | B02 | 4x12 | 17 | | | 1 | EA |
| 6 | DOOR HEADER | | 4X8 | 4 | | | 1 | EA |
| 7 | WINDOW HEADER | | 4X8 | 7 | | | 7 | EA |
| 8 | WINDOW HEADER | | 4X8 | 5 | | | 2 | EA |
| 9 | WALL S.R. Main (Optional) | | 1/2" | | 71 | | 621 | SF |
| 10 | CEILING S.R. Main (Optional) | | 1/2" | | | | 1008 | SF |
| 11 | WALL S.R. Upper (Optional) | | 1/2" | | 124 | | 899 | SF |
| 12 | CEILING S.R. Upper (Optional) | | 1/2" | | | | 1008 | SF |
| 13 | FLOOR PLYWOOD | | 3/4" | | | | 1008 | SF |
| 14 | WALL SHEATH | | 1/2" CDX | | 71 | | 1256 | SF |
| 15 | WALL VAPOR | | 15# Felt | | 71 | | 1256 | SF |
| 16 | SIDING | | | | 71 | | 1256 | SF |
| 17 | CONCRETE (Footing) | | 12"x6" | | | | 2.44 | CY |
| 18 | CONCRETE (Wall) | | 6" x 20" | | | | 4.07 | CY |
| 19 | CONCRETE (Floor) | | 4" | | | | 12.32 | CY |
| 20 | RAFTERS | | Scissor Truss | 24' + O.H. | 42 | 24 | 22 | EA |
| 21 | ROOF SHEATH | | 1/2" CDX Plywood | | | | 1239 | SF |
| 22 | ROOF FELT | | 30# Felt | | | | 1239 | SF |
| 23 | ROOFING | | Composition | | | | 1239 | SF |
| 24 | EAVE BLOCKING | | 2X4 | 22.5 | 84 | 24 | 42 | EA |
| 25 | H2.5 RAFTER TIE | | | | 84 | 24 | 44 | EA |
| 26 | FLOOR JOISTS | B01 | (see Plan) | 24' | 42 | 16 | 32 | EA |
| 27 | HD5A (See Plan) | | | | | | 2 | EA |
| 28 | SSTB20 | | | | | | 2 | EA |