

MATERIAL LIST

G4848A Garage Plan

Standard W/ Truss Roof

This estimate is designed solely to provide the customer with a rough estimate of the amount of material used in the given project. The material estimate is based on normal and typical building and construction techniques. The actual amount of material used may vary from this estimate due to a number of factors. Consequently, no representation or warranty has been made that the amount of material used will not vary from the estimate.

	ITEM	CALC	SIZE	LENGTH	O.C.	QTY	
1	MAIN EXT STUDS		2X6	113.50	16"	110	EA
2	MAIN TREATED SILL		2X6			147	LF
3	MAIN INT PLATES		2X4			36	LF
4	MAIN EXT PLATES		2X6			576	LF
5	MAIN INT STUDS		2X4		16"	11	EA
6	UPPER EXT STUDS		2X6	93.00	16"	72	EA
7	UPPER EXT WALL PLATES		2X6			192	LF
8	UPPER INT PLATES					135	LF
9	UPPER INT WALL STUDS			VARIES	16"	35	EA
10	UPPER CEILING S.R. (Optional)		1/2" GYP.			729	SF
11	UPPER EXT WALL S.R. (Optional)		1/2" GYP.			1008	SF
12	HEADER, (Upper Window)		4X8	5'		6	EA
13	HEADER, (Ext Main Door)		4X8	4'		1	EA
14	HEADER, (Ext Main Door)		3-1/8X12 GLB	17'		2	EA
15	HEADER, (Ext Main Door)		4X12	11'		1	EA
16	TRUSSES				24"	23	EA
17	TRUSSES				24"	46	EA
18	TRUSSES (Ends)					2	EA
19	TRUSSES (Ends)					4	EA
20	EAVE BLOCKING		2X	22.5"	24"	96	EA
21	H2.5 RAFTER TIE				24"	75	EA
22	ROOF SHEATH		1/2" CDX			2850	SF
23	ROOF FELT		30# Felt			2850	SF
24	ROOFING					2850	SF
25	BARGE RAFTERS		2X6	28'		4	EA
26	MAIN EXT WALL S.R. (Optional)		1/2" GYP.			1470	SF
27	MAIN INT WALL S.R. (Optional)		1/2" GYP.			240	SF
28	MAIN CEILING S.R. (Optional)		1/2" GYP.			2304	SF
29	EXT WALL SHEATH		1/2" CDX			3006	SF
30	EXT WALL VAPOR		15# Felt			3006	SF
31	EXT SIDING (See Plan)		Varies			3006	SF
32	CONCRETE					47.44	CY
33	JOISTS	B03	2X10	16'	16"	37	EA
34	UPPER FLOOR PLYWOOD		5/8"			2304	SF
35	BEAM	B02	6-3/4X18 GLB	48'		2	EA
36	POST		6X6	10'		12	EA
37	ANCHOR BOLTS		1/2"		48"	37	EA
38	HOLD DOWNS		HD2A W/SSTB16			12	EA
39	WIRE MESH		6X6 W1.4 X W1.4			2304	SF